

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 093-20312-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date spud 6/20/76.

Well Operator: XTO Energy, Inc. KCC License #: 32864
(Owner/Company Name) (Operator's)
Address: 210 Park Ave., Suite 2350 City: Oklahoma City
State: Oklahoma Zip Code: 73102 Contact Phone: (405) 319-3212
Lease: Campbell Well #: 11-2 Sec. 23 Twp. 25 S. R. 36 East West
SE - SE - SE - NW Spot Location / QQQQ County: Kearny

2540 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)
2490 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: N/A Set at: _____ Cemented with: _____ Sacks _____
Surface Casing Size: 8 5/8" Set at: 554 Cemented with: 300 Sacks _____
Production Casing Size: 4 1/2" Set at: 3010' KB Cemented with: 700 Sacks _____
List (ALL) Perforations and Bridgeplug Sets: 2714'-28', 2734'-36', 2748'-52', 2760'-64', 2780'-84', 2798'-2802'

Elevation: 3037' (G.L. / K.B.) T.D.: 3030' P.B.T.D.: 2998' Anhydrite Depth: 1230'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole
Proposed Method of Plugging (attach a separate page if additional space is needed): 25 sx cmt @ 2600' - 2900' 29.5 yield, 60 sx cmt @ 1000' - 800' 70.8 yield, 85 sx @ 650' - 400' 100.8 yield, & 10 sx cmt @ 34' - 4' 11.8 yield Mud weight - minimum 9 ppg, cement weight - minimum 16 ppg

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No
If not explain why? Unknown

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: David Littell or Mark Gosch
Phone: (620) 355-7838
Address: 805 S. Hwy 25 City / State: Lakin, KS 67860
Plugging Contractor: Sargent & Horton Plugging KCC License #: 31151
(Company Name) (Contractor's)
Address: Rt. 1, Box 49 BA, Tyrone, OK Phone: (580) 854-6515

Proposed Date and Hour of Plugging (if known?): ASAP 6-12-06 - 1:00pm

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 5/31/06 Authorized Operator / Agent: Karen Byers
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

** Well already plugged - Dlg - Kcc - 6/19/06*

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 19 2006

CONSERVATION DIVISION
WICHITA, KS

*Dist
01*