

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED

JUN 22 2006

KCC WICHITA

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: H & B Petroleum Corporation

Address: PO Box 277, Ellinwood, Kansas 67526-0277

Phone: (620) 564-3002 Operator License #: 32158

Type of Well: SWD Docket #: 16038 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: (Date)

by: David Williams (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Mississippi Depth to Top: 5104 Bottom: 5235 T.D. 5294

API Number: 15-097-20089-00-01

Lease Name: Rogers C

Well Number: 1

Spot Location (QQQQ): C - NE - NE -

4615 Feet from North / South Section Line

662 Feet from East / West Section Line

Sec. 8 Twp. 30 S. R. 19 East West

County: Kiowa

Date Well Completed: 08-01-1979

Plugging Commenced: 06-15-2006

Plugging Completed: 06-16-2006

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Mississippi SWD casing data.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Set CIBP @ 5000' w/ 4 sks cmt. 1400' 80 sks cmt 2 sks hulls. 1200' Pump 15 sks gel 300# hulls & 75 sks cmt. 480' Pump 50 sks.

40' Pump 15 sks cmt. All cmt 60/40 Pos w/ 6% gel. Top off w/ ready mix 06-19-2006.


Name of Plugging Contractor: Xtreme Well Service, Inc. License #: 33369

Address: PO Box 31, Russell, Kansas 67665

Name of Party Responsible for Plugging Fees: H & B Petroleum Corporation

State of Kansas County, Barton, ss.

Al Hammersmith (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Handwritten Signature]

(Address) PO Box 277, Ellinwood, Kansas 67526-0277

SUBSCRIBED and SWORN TO before me this 21st day of June, 2006

Lynnae M. Partridge My Commission Expires: January 3, 2010