



15-181-20011-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 11 1972  
CONSERVATION DIVISION  
Wichita, Kansas

1/11/72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Tom Buffington of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: U. S. Signal Oil & Gas Company, 1971 Program.

Complete Address: 125 Central Building, Midland, Texas .

Lease Name: Signal '71 Baird Well No. 1

Location: CNE-NW Sec. 4 Twp. 7 Rge. (E)(W) 37

County: Sherman Total Depth 5568' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Buffington was instructed to plug the well as follows:

445'--8 5/8" Surface casing, cement circulated with 300 Sx.  
Top of Dakota section @ 1918'.

Circulate hole with heavy mud. Pull DP to 2175' and displace 110 Cu. Ft. cement thru DP. Pull DP to 465' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Fisher  
Conservation Division Agent