

State of Kansas



15-181-20009-00-00

ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 2 1969  
CONSERVATION DIVISION  
Wichita, Kansas

a/2/69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Oller of Murfin Drlg. has this date requested permission to plug the following described well:

Mr. Oller guarantees payment of the plugging fee.

Operator's full Name: Slawson Donald C. Slawson

Complete Address: 408 one twenty Bldg., Wichita, Ks.

Lease Name: Wolfrun "B" Well No. 1

Location: G NE NW Sec. 4 Twp. 7 Rge. (E)(W) 39

County: Sherman Total Depth 3280' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Oller was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 2280' and displace  
70 sk cmt thru drill pipe. Heavy mud to 330' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Mansueti  
Conservation Division Agent