

State of Kansas



15-181-20003-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Swede Holaday of Mack Oil Company, has this date requested permission to plug the following described well:

Mr. Holaday guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company,

Complete Address: 812 Union Center Building, Wichita, Kansas.

Lease Name: Bair Well No. 1

Location: CNW-SW Sec. 18 Twp. 7 Rge. (E)(W) 41

County: Sherman Total Depth 5470' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Holaday was instructed to plug the well as follows:

384'--8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota section @ 2495'.

Circulate hole with heavy mud, pull DP to 2725' and displace 120 Sx.
cement thru DP. Pull DP to 425' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 30' with 1/2 sack hulls and 5 Sx. cement to bottom
of cellar.

RECEIVED
 STATE CORPORATION COMMISSION

JAN 16 1969

CONSERVATION DIVISION
 Wichita, Kansas

1/16/69

Very truly yours,

Conservation Division Agent