

State of Kansas



15-065-D1308-00-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1969
CONSERVATION DIVISION
Wichita, Kansas

4/21/69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Lynch of Lynch Casing Pulling Company has this date requested permission to plug the following described well:

Mr. Lynch guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe and Supply, Incorporated,

Complete Address: Box #169, Russell, Kansas.

Lease Name: Wanker Well No. A-1,

Location: SENE
CSW-NE Sec. 35 Twp. 7 Rge. (E)(W) 23

County: Graham Total Depth 3765' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lynch was instructed to plug the well as follows:

230'--8 5/8" Surface casing, cement circulated with 175 Sx.

3765'--5 1/2" Production casing cemented on bottom with 125 Sx. No Plug Back nor perforations indicated.

Push plug to 3500', sand back to 3475' and set 5 Sx. cement with dump bailer.

Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 130

Sx. cement, staged.

Very truly yours,

Conservation Division Agent