

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25440-00-00  
Spot: SWNWNW Sec/Twnshp/Rge: 13-14S-16W  
1100 feet from N Section Line, 330 feet from W Section Line  
Lease Name: HAMMERSCHMIDT Well #: 1-13  
County: ELLIS Total Vertical Depth: 3500 feet

Operator License No.: 30717  
Op Name: DOWNING-NELSON OIL CO INC  
Address: PO BOX 372  
HAYS, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3498	2630	150 SX CMT
SURF	8.625	214	0	150 SX CMT

# 113.15

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/19/2006 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/19/2006 1:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing to 3080' and topped with 5 sxs cement using a dump bailer.  
Cut casing free at 2630'.  
Pulled up to 1650' - mixed and pumped 110 sxs cement with 300# hulls.  
Pulled up to 1000' - spotted with 40 sxs cement and 100# hulls.  
Pulled up to 600' - spotted 30 sxs cement and 100# hulls.  
Pulled up to 150' and circulated cement with 40 sxs.  
POOH Hole full of cement.

Perfs:

Top	Bot	Thru	Comments
3370	3373		
3292	3296		
3227	3232		
3206	3210		
3159	3163		
2132	3135		

Remarks: QUALITY CEMENTING COMPANY.

Plugged through: CSG

INVOICED  
DATE 6-26-06  
TEL. NO. 200 606 61843

District: 04

Signed

(TECHNICIAN)

RECEIVED

JUN 23 2006

KCC WICHITA

JUN 20 2006

PCP

DOWNING-NELSON OIL CO  
HAYS KS 67601

WILDCAT

13-14S-16W  
110'S, C SW NW NW

#1-13 HAMMERSCHMIDT

site 1/2 S & 4-1/2 E OF VICTORIA KS      city: ELLIS      AP# 15-051-25440  
cont: DISCOVERY DRILLING #3      field WC (5/8 SW OF  
geol: RON NELSON      HAMMERSCHMIDT)  
fr      spd      drig      card      last  
date 07/27/2005      date 09/27/2005      comp 10/03/2005      issued 03/06/2006      revised 04/10/2006

#			

ELV: 1898 KB, 1890 GL LOG  
tops.....depth/datum  
ANH.....978 +920  
B/ANH.....1016 +882  
TOP.....2856 -958  
HEEB.....3082 -1184  
TOR.....3100 -1202  
LANS.....3132 -1234  
BKC.....3364 -1466  
ARB.....3420 -1522  
RTD.....3500 -1602

IP status  
D&A, ARB, 01/15/2006  
NOTE: INFO RELEASED 4/10/2006 - WAS D & A - TIGHT HOLE  
CSG: 8-5/8" 213.9 / 150 SX (ALT 2), 5-1/2" 3497.74 / 150 SX, MULTI STAGE COLLAR AT 941  
NO CORES  
DSTS TAKEN - DETAILS NA  
TRGT ZN: LKC, ARB (OIL), PTD 3500 (ARB), MICT (10/4/2005) - CO, PF (LANS) 3132-3135, W / 4 SPF, AC 1000 GAL (15% MA), SWB LD, SO, SET 2-3/8" TBG AT 3215, PKR AT 3220, P 2 BOPD, NW, NSG, DOFP 11/25/2005; WELL PUMP LESS THAN 200 BO TOTAL & QUICKLY DECL TO NON-COMMERCIAL; NO OIL SOLD; DECISION MADE TO P & A 1/15/2006 (SHOW HOLE) - NO OTHER INFO AVAILABLE - TEMP COMP 4/10/2006

COPYRIGHT 2006  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS