

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-19095-00-01  
Spot: SESESW Sec/Twnshp/Rge: 2-18S-14W  
330 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: EVELEIGH A Well #: DO1  
County: BARTON Total Vertical Depth: 3550 feet

Operator License No.: 7023  
Op Name: KLIMA WELL SERVICE, INC.  
Address: 610 WEST FRONT STREET  
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3361	0	w/125 sxs cmt
SURF	8.625	842	0	w/200 sxs cmt
T1	3	3339		

# 115.38

Well Type: SWD UIC Docket No: D16519.0 Date/Time to Plug: 06/07/2006 9:00 AM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: DON BROWNING Company: KLIMA WELL SERVICE, INC. Phone: (620) 786-7063

Proposed Plugging Method: Ordered 420 sxs 60/40 pozmix - 10% gel with 1/4# flocele - 600# hulls.  
Brought another 250 sxs 60/40 pozmix and 500# hulls.  
Log Tech perfed at 845' and 1450'.  
Junk in the hole.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/07/2006 5:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 2150'.  
Rigged to tubing and pumped 100 sxs cement with 300# hulls mix in - no circulation.  
Pulled tubing to 1500' - pumped 320 sxs cement with 300# hulls mixed in - no cement circulated.  
Pulled tubing - ordered an additional 250 sxs cement and 500# hulls.  
RIH with tubing to 875' - pumped 120 sxs cement with 350# hulls mixed into circulate cement out of 5 1/2" casing.  
Shut in 5 1/2" casing and pumped 75 sxs cement with 50# hulls to circulate cement out of 8 5/8" casing.  
Pulled tubing and rigged to 5 1/2" casing with a swedge - pumped 50 sxs cement.  
Max. P.S.I. 250#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3362	3550		OH

Remarks: COPELAND SERVICE ACID-TICKET #C030470.

Plugged through: TBG

INVOICED  
6-26-06  
DATE 20060618  
TIME 14:44

District: 04

Signed [Signature]  
(TECHNICIAN)

RECEIVED

JUN 23 2006

KCC WICHITA

JUN 20 2006

pet

B. B. BLAIR & DERBY OIL

#1

EVELEIGH

2-18-14W

SE SE SW

Contr.

BARTON

County

E 1886RB

Comm.

Comp.

8-3-51

IP

181 BOPD

PHY POT

Tops	Depth	Datum
ANH	830	1056
BR LM	3127	-1241
LANS	3138	-1252
CONG	3340	-1454
ARB	3359	-1473
T.O.D.	3372	-1486

Casing

8" 842  
5" 3361

DST 3206-16, 1 HR,  
REC 86' MUD:  
DST 3359-64, 1.5 MIN,  
10' MUD:  
SWB 2 BOPH  
ACID 250  
SWB 4 1/2 BOPH/10 HRS

BOYD POOL


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS