

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-00872-00-00
Spot: SESWNE Sec/Twnshp/Rge: 22-13S-17W
2310 feet from N Section Line, 1650 feet from E Section Line
Lease Name: VON LINTEL Well #: 1
County: ELLIS Total Vertical Depth: 3558 feet

Operator License No.: 5145
Op Name: DREILING OIL INC
Address: 1008 CODY AVENUE PO BOX 550
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3552	0	150 SX
SURF	8.625	120	0	120 SX

\$ 115.64

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/22/2006 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: IVAN EDSEL Company: DREILING OIL, INC. Phone: (785) 735-4008

Proposed Order 325 sxs 60/40 pozmix - 10% gel - 800# hulls.
Plugging Low fluid level. Appears to be squeezed but no records.
Method: Perfs from 3246' - 3552'.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 06/22/2006 11:00 AM KCC Agent: HERB DEINES

Actual Plugging Report:

Perforated casing at 1850' - 1225' - 625' with 2 SPF.
Tied onto annulus - pumped 10 sxs cement with 500# max. pressure.
Tied onto production casing and pumped 315 sxs cement with 800# hulls.
Max. P.S.I. 700#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3546	3552		
3541	3546		
3529	3532		
3521	3524		
3495	3497		
3475	3477		
3452	3454		
3406	3409		
3346	3349		
3326	3329		
3316	3320		
3292	3304		
3246	3250		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

RECEIVED
JUN 26 2006
KCC WICHITA

INVOICED

Signed



(TECHNICIAN)

DATE

6-27-06

AMOUNT

2006061850

Form CP-2/3

JUN 22 2006

PCT

L J WILLIAMSON

#1

VON LINTEL

22-13-17W
SE SW NE

Contr.

ELLIS

County

E 1986RB

Comm.

Comp.

8-20-54

IP

209 BOPD

Tops	Depth	Datum
TOR	3240	-1254
LANS	3269	-1283
KC	3270	-1284
B/KC	3462	-1476
ARB	3518	-1532
TD	3553	-1567

Casing

8" 120

5" 3552

DST 3285-3301/-, 620' GCO

BHP 840#:

CO 3553: 24/3541-46: TST

3 GFPH: ACID 500: DD 3556


PERF 30/3546-52: PB 3475

76/3292-3304: SWB 35 BOPH,

CATHARINE SO POOL NO WTR

ACID 3000: SWB

47 BOPH:



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

2 1/2