

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21304-00-00
Spot: W2SESW Sec/Twnshp/Rge: 15-7S-19W
660 feet from S Section Line, 3630 feet from E Section Line
Lease Name: BURTON Well #: 2
County: ROOKS Total Vertical Depth: 3390 feet

Operator License No.: 9957
Op Name: THOMASON PETROLEUM, INC
Address: 301 W 13TH ST PO BOX 875
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3389	0	w/175 sxs cmt
SURF	8.625	330	0	w/180 sxs cmt

\$ 110.18

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/15/2006 1:00 PM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: STEVE THOMASON Company: THOMASON PETROLEUM, INC. Phone: (785) 625-9045

Proposed Plugging Method: Ordered 205 sxs cement and 600# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/15/2006 3:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

DV at 1450' with 400 sxs cement.
Ran tubing to 2500' - circulated with 185 sxs cement and 500# hulls.
Pulled all tubing - squeezed 5 1/2" casing with 27 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
Tied to 8 5/8" x 5 1/2" annulus - squeezed 20 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.
Total of 232 sxs 60/40 pozmix - 10% gel and 500# hulls.

Perfs:

Top	Bot	Thru	Comments
3281	3287		
3262	3264		

INVOICED
DATE: 6-27-06
2006061855

RECEIVED
JUN 26 2006

Remarks: ALLIED CEMENTING COMPANY. KELLER TANK-WATER.

Plugged through: TBG

KCC WICHITA

District: 04

Signed

Roger D. Moses

(TECHNICIAN)


C
W
C
C

REPLACEMENT CARD

THOMASON OIL COMPANY
2700 OAK ST. #A #2 BURTON 15-7-19W
HAYS, KS 67601 C W/2 SE SW
CONTR PIONEER DRILLING CO. CTY. ROOKS 100'E

GEOLOGICAL FIELD GROVER

ELV 1914 KB SPD 7/31/81 CARD ISSUED 1/21/82 P 8 BO & 2 BWPD
1909 GL KC 3262-3287 OA
API 15-163-21,304



LOG	Top	Depth/Datum
ANH	1414+ 500
B/ANH	1449+ 465
HEEB	3066-1152
TOR	3097-1183
LANS	3108-1194
ARB	NOT REACHED
RTD	3390-1476

8 5/8 " 330.35 / 180 SX, 5 1/2 " 3389 / 175 SX
NO CORES OR DSTS
MCT - CO, PF (KC) 3262-3264 & 3281-3287, AC 2000 GAL
(15%), POP, P 8 BO & 72 BWPD, 10/15/81

INFO RELEASED: 1/1/87 - ADDED LOG TOPS
NOTE: DUPLICATE FILING - WAS ABD LOC, THOMASON OIL, #2
SCHNEIDER, SW SW SE, 21-7-19W, INFO RELEASED: 9/11/86 -
RE-ISSUED CARD TO COMBINE INFO FROM TWO PREVIOUSLY IS-
SUED CARDS DATED 6/25/81 & 1/21/82

COPYRIGHT 1987
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS