

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00700-00-00
Spot: NWNENE Sec/Twnshp/Rge: 1-11S-21W
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: SPAULDING B Well #: 3
County: TREGO Total Vertical Depth: 3657 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| CIBP | | 3645 | | |
| PROD | 5.5 | 3650 | 0 | 100 SX |
| SURF | 8.625 | 183 | 0 | 175 SX |

\$ 118.85

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/19/2006 12:00 PM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9169

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 13 sxs gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/19/2006 3:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Squeezes at: 873' w/38 sxs - 880' w/150 sxs - 1215' w/150 sxs - 1433' w/10 sxs - 1538' w/150 sxs - 2936' w/135 sxs.
Ran tubing to 3000' - spotted 12 sxs gel followed with 50 sxs cement and 300# hulls on bottom.
Pulled tubing to 1500' - circulated with 120 sxs cement.
Pulled tubing - squeezed 5 1/2" casing with 20 sxs cement and 200# hulls.
Max. P.S.I. 500#. S.I.P. 500#.
Tied to 8 5/8" x 5 1/2" annulus - squeezed 5 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.
Total of 190 sxs 60/40 pozmix - 10% gel - 12 sxs gel - 500# hulls.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3650 | 3682 | | OH |
| 3634 | 3637 | | |
| 3544 | 3550 | | |
| 3112 | 3142 | | |

INVOICED
DATE 6-27-06
BY 2006061856

RECEIVED
JUN 26 2006

Remarks: ALLIED CEMENTING COMPANY. STEWART TANK-WATER.

Plugged through: TBG

KCC WICHITA

District: 04

Signed Roger L Moses
(TECHNICIAN)

JUN 22 2006

PKA

IMPERIAL

IMPERIAL OIL COMPANY #3 SPAULDING 'B' 11-1-21W
MOWINE NE

Contr. IMPERIAL OIL TREGO County

E 2077RB Comm. 12-3-56 Comp. 1-25-57 IP 276 8:00PD/ARB
PHY PWT

| Tops | Depth | Datum |
|------|-------|-------|
| ANH | 1528 | 549 |
| HEEB | 3313 | -1236 |
| TOR | 3335 | -1258 |
| LANS | 3351 | -1274 |
| | | |
| CONG | 3607 | -1530 |
| SIMP | 3629 | -1552 |
| ARB | 3646 | -1569 |
| | | |
| TD | 3657 | -1580 |

Casing
 8" 183
 5" 3650
 DST 3431-43/2 HRS, 124' WTR, SSO
 BHP 1185#
 DST 3447-60/2 HRS, 80' WTR,
 BHP 1150#
 DD 3657: SWB 9 BOPH/12 HRS:
 ACID 1000: SWB 12 BOPH/10 HRS

SPAULDING

| | | |
|--|--|--|
| | | |
| | | |
| | | |

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS