

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-21112-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 3-16S-16W  
1650 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: MCCONNELL Well #: 1-A  
County: RUSH Total Vertical Depth: 3528 feet

Operator License No.: 33612  
Op Name: GEIST, RON DBA WILDCAT WELL SER  
Address: PO BOX 961  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3516	2526	WITH 175 SX CMT
SURF	8.625	1001		

# 114.666

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/09/2006 10:30 AM  
Plug Co. License No.: 33612 Plug Co. Name: GEIST, RON DBA WILDCAT WELL SERVICE  
Proposal Rcvd. from: RON GEIST Company: GEIST, RON DBA WILDCAT WELL Phone: (785) 728-2040

Proposed Plugging Method: SAND TO 3450' & 4 SX CMT. PLUG AT 1030' WITH 10 SX GEL - 50 SX CMT. PLUG AT 500' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/09/2006 5:55 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3450' & 4 SX CMT WITH BAILER. PUMP PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1030' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 500' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3516	3528	OH	

INVOICED  
DATE 6-27-06  
INT. NO. 2006061852  
RECEIVED  
JUN 26 2006  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED  
JUN 14 2006  
KCC Dodge City

Signed Richard M. Lucy  
(TECHNICIAN)

Form CP-23  
PKT