

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-04899-00-00
Spot: SWSENW Sec/Twnshp/Rge: 34-11S-17W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease Name: HAUSER Well #: 3
County: ELLIS Total Vertical Depth: 3654 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3689	0	w/150 sxs cmt
SURF	8.625	1348	0	w/unknown sxs cmt

\$ 118.76

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/20/2006 9:30 AM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9169

Proposed Plugging Method: Ordered out 360 sxs 60/40 pozmix - 10% gel - 14 sxs gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/20/2006 2:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Perforated casing at 425' - 1090'.
TIH with tubing to 2600' - mixed and pumped 13 sxs gel followed with 40 sxs cement and 300# hulls.
Pulled up to 1500' - spotted 100 sxs cement with 200# hulls.
Pulled up to 750' - circulated cement with 100 sxs.
POOH. Swaged onto 4 1/2" casing and pumped 120 sxs - circulated cement up 8 5/8".
Shut in.

INVOICED
DATE 6-27-06
2006061856

RECEIVED
JUN 26 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

HD.

Signed Jay Pfeifer (TECHNICIAN)

JUN 22 2006

ACT