

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01553-00-00
Spot: SEWNNE Sec/Twnshp/Rge: 21-9S-18W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease Name: PARADISE CREEK Well #: 203
County: ROOKS Total Vertical Depth: 3635 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3576	0	150 SX
SURF	8.625	1488	0	850 SX

\$ 118.14

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/21/2006 9:30 AM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9169

Proposed Plugging Method: Ordered out 280 sxs 60/40 pozmix - 10% gel - 14 sxs gel - 500# hulls.
Squeezed at 2500' w/300 sxs to surface.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/21/2006 12:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 3000' - mixed and pumped 14 sxs gel followed with 50 sxs cement with 300# hulls.
Pulled up to 1500' - circulated cement up 5 1/2" with 140 sxs cement.
POOH. Swaged onto 5 1/2" casing and circulated cement up 8 5/8" with 20 sxs.
Shut in annulus and topped with 40 sxs cement with 200# hulls.
S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3576	3635		OPEN HOLE

INVOICED
DATE 6-27-06
WT. NO. 2006061856

RECEIVED

JUN 26 2006

KCC WICHITA

Remarks: LEASE ALSO KNOWN AS HILGERS A-3. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

Form CP-2/3

JUN 22 2006

ACT