

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-01764-00-02
Spot: SWSENE Sec/Twnshp/Rge: 1-32S-6E
2990 feet from S Section Line, 1128 feet from E Section Line
Lease Name: BROOKS Well #: 4
County: COWLEY Total Vertical Depth: 2953 feet

Operator License No.: 32475
Op Name: BRADEN, JAMES R. DBA BRADEN PET
Address: 725 OAK ST. P.O. BOX 282
BURDEN, KS 67019

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	10.75	120		125 SX
PROD	4.5	2953		
SURF	7	2255		200 SX

\$95.07

Well Type: SWD UIC Docket No: D24368.0 Date/Time to Plug: 03/21/2006 12:00 PM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: JAMES BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 438-2856

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 03/28/2006 4:35 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

3/21/2006 -- Sanded back 50' above perforations at 1690'. Dump bailed 4 sacks of cement on top.

3/28/2006 -- RIH with tubing at 350'. Braden Petroleum mixed and pumped 85 sacks of 60/40 posmix with 4% gel to surface.

Cement at surface between 10-3/4" and 7"

1985 -- Pumped 120 sacks of cement between 10-3/4" and 7"

4-1/2" liner from 1658' - 2953'

Perforations 1748' - 1780'

CIBP at 2251'

Perfs:

Top	Bot	Thru	Comments
1748	1780		
RECEIVED KCC DISTRICT #2 MAY 26 2006 WICHITA, KS			
INVOICE			

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)

RECEIVED
JUN 23 2006
KCC WICHITA

Form CP-2/3

ACT