

3 023054

15001-02104-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER

CONTROL NO. 20050052-013

~~SE~~ NW,SE,SW 1/4 Sec/Twp/Rge S.8-T.26S.-R.18E.

890 feet from south section line

3353 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License #

~~100~~ 107

Lease/Well#

NELSON NO.13

County

ALLEN

Operator: STATE OF KANSAS

Well Total Depth

750 feet

Name & FEE FUND PLUGGING

Production Pipe: 2"

Size Feet

750

Address

Surface Casing: 7"

Size Feet

20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐D & A ☐

Other well as hereinafter indicated:

Plugging Contractor: SPLANE PULLING & ROUSTABOUT SERVICE

Lic. #

6372

Address: P.O. BOX 386, CHANUTE, KANSAS 66720

Company to plug at: Hour: 11:00A.M. Day: 11 Month: 4 2006

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone:

620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 750' THAT

HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THS PLUGGING PROPOSAL

WAS TO CIRCULATE THE 2" CASING FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All ☐Part ☐

TECHNICIAN

None ☐X ☒

Operations Completed: Hour:

2:00P.M. Day:

11 Month:

4

2006

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2" CASING TO 750'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT

SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.


30 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.13) (NO OTHER NUMBER IS AVAILABLE FOR THIS WELL.)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:


TECHNICIANRECEIVED
APR 17 2006
KCC WICHITA