

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

JUN 27 2006

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

KCC WICHITA

065-20392-00-01

Lease Operator: Murfin Drilling Company, Inc.

Address: 250 N. Water, Suite 300

Phone: (316) 267-3241 Operator License #: 30606

Type of Well: Oil SMD EOR Docket #: E-19789.1
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: KCC 6/27/06 (Date)

by: Per CP 213 (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

4014-4076 LKC Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - Docket E-19,789-

Lease Name: Hoeting Unit

Well Number: 2-5

Spot Location (QQQQ): SW - SE - NE -

2970 Feet from North / South Section Line

990 Feet from East / West Section Line

Sec. 29 Twp. 9 S. R. 24 East West

County: Graham

Date Well Completed: 11/70

Plugging Commenced: 6/13/06

Plugging Completed: 6/13/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	266	8 5/8	266	0
	Production	Surface	4131	4 1/2	4131	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RU Perf Tech. Perforate 5 1/2 csg @ 2250' & 1100', 2 SPF. RIH with 2 3/8" tbg @ 2298'. RU Swift Services. Pumped 85 sx SMD & 300# hulls, to circ cmt to surface. TOH with 2 3/8" tbg. Tied onto 4 1/2 csg. Pumped 45 sx SMD, 125# hulls, max pressure 400#, ISIP 300#. Tied onto 8 5/8". Pumped 60 sx, 75# hulls, max press 100#, ISIP 50#. Plugged @ 2:30 pm. No state man on location. Called report to Herb Deines w/KCC.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606


Address: 250 N. Water, Suite 300 ; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.

State of Kansas County, Sedgwick, ss.

Susan Sears, Petroleum Engineer (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Susan Sears

(Address) 250 N. Water, Suite 300; Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 23rd day of June 20 06

Susan Brady My Commission Expires: 11-4-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

POST