

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
**This Form must be Typed  
Form must be Signed  
All blanks must be Filled**

API # 15 - 093-20304--00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date spud 6/14/76

Well Operator: XTO Energy, Inc. KCC License #: 32864

Address: 210 Park Ave., Suite 2350 (Owner / Company Name) City: Oklahoma City (Operator's)

State: Oklahoma Zip Code: 73102 Contact Phone: ( 405 ) 319 - 3212

Lease: Masonic Home Well #: 4-2 Sec. 35 Twp. 25 S. R. 36  East  West

SW - SW - SW - NE Spot Location / QQQQ County: Keamy

*per oper KCC-DW* 2950 2590 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

2490 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well

SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: N/A Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks \_\_\_\_\_

Surface Casing Size: 8 5/8" Set at: 575 Cemented with: 300 Sacks \_\_\_\_\_

Production Casing Size: 4 1/2" Set at: 3017 Cemented with: 700 Sacks \_\_\_\_\_

List (ALL) Perforations and Bridgeplug Sets: 2706' - 16', 2722' - 28', 2740' - 46', 2752' - 56', 2762' - 66', 2770' - 74', 2792' - 96'

Elevation: 3036' ( G.L. /  K.B.) T.D.: 3021' PBD: 3017' Anhydrite Depth: 1233'

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole (Stone Corral Formation)

Proposed Method of Plugging (attach a separate page if additional space is needed): CIBP @ 2656 w/ 2 sx cmt, 60 sx cmt @ csg cut +/- 1000' - 800' plug 70.8 yield, 85 sx cmt @ 675 - 425' 100.8 yield, 10 sx cmt @ 34'-4' 11.8 yield Mud weight - minimum 9 ppg, cement weight - minimum 16 ppg

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? Unknown

**Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.**

List Name of Company Representative authorized to be in charge of plugging operations: David Littell or Mark Gosch

Phone: ( 620 ) 355 - 7838

Address: 805 S. Hwy 25 City / State: Lakin, KS 67860

Plugging Contractor: Sargent & Horton Plugging KCC License #: 31151

Address: Rt. 1, Box 49 BA, Tyrone, OK (Company Name) Phone: ( 580 ) 854 - 6515 (Contractor's)

Proposed Date and Hour of Plugging (if known?): ASAP 6/08/06 - 1:00pm

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5/31/06 Authorized Operator / Agent: Karen Byers (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Well already plugged - DW-KCC-6/14/06*

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 19 2006  
CONSERVATION DIVISION  
WICHITA, KS

*Dist  
01*