

RECEIVED

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

JUN 22 2006

Form CP-1  
September 2003

WELL PLUGGING APPLICATION **KCC WICHITA**

This Form must be Typed  
This Form must be Signed  
All blanks must be Filled

Please TYPE Form and File ONE Copy

API # 15 - 081-20-645-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date August 13, 1990.

Well Operator: Kansas Natural Gas Operating, Inc. KCC License #: 32787  
(Owner / Company Name) (Operator's)

Address: P.O. Box 815 City: Sublette

State: Kansas Zip Code: 67877 Contact Phone: ( 620 ) 675 - 8185

Lease: H. McCoy Well #: 1-2 Sec. 36 Twp. 29 S. R. 33  East  West

App. - Center - SW - 1/4 Spot Location / QQQQ County: Haskell

1250' Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

4030' Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: None Set at: X Cemented with: X Sacks

Surface Casing Size: 8 5/8" - 24# Set at: 600' Cemented with: 280 - Common Sacks

Production Casing Size: 5 1/2" - 14# Set at: 2748' Cemented with: 580 Sacks Class "C" Sacks

List (ALL) Perforations and Bridgeplug Sets: 2664' - 2672', 2683' - 2693', 2708' - 2716', 2738' - 2744'

128 Total Shots

Elevation: 2941' ( G.L. /  K.B.) T.D.: 2760' PBTD: 2755' Anhydrite Depth: 1864'  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Set cast iron bridge plug over perms at approximately 2610'. Use wireline bailer to dump (2) sacks of cement on top of plug. Run mud spacer to approximately 1700'. Spot pump 20 sacks of cement. Run mud spacer to approximately 700' then fill 5 1/2" casing to surface with cement.

Hook onto backside & check to see if we have good cement on surface pipe. Complete plug job by cutting 8 5/8" & 5 1/2" casing off 6' below ground, cap off & backfill.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Steve Lehning

Phone: ( 620 ) 675 - 8185

Address: P.O. Box 815 City / State: Sublette, KS 67877

Plugging Contractor: Halliburton KCC License #: 5287-99997  
(Company Name) (Contractor's)

Address: Liberal, Kansas Phone: ( 800 ) 853 - 3555

Proposed Date and Hour of Plugging (if known?): As soon as new well is tied into pipeline.

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: June 21, 2006 Authorized Operator / Agent: Steve Lehning FOR KANSAS NATURAL GAS OPER, INC.  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Can*

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Kansas Natural Gas Operating, Inc.  
PO Box 818  
1200 Main Street  
Hays, KS 67601

June 28, 2006

Re: H McCOY #1-2  
API 15-081-20645-00-00  
SW 36-29S-33W, 1250 FSL 4030 FEL  
HASKELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888

Sincerely  


David P. Williams  
Production Supervisor