

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION  
Please TYPE Form and File ONE Copy

RECEIVED  
JUN 22 2006  
KCC WICHITA

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - Drilled in 1947 055-00483-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date January 1, 1947.

Well Operator: Kansas Natural Gas Operating, Inc. KCC License #: 32787

Address: P.O. Box 815 (Owner / Company Name) City: Sublette (Operator's)

State: Kansas Zip Code: 67877 Contact Phone: ( 620 ) 675 - 8185

Lease: Finnup Well #: 1 Sec. 19 Twp. 24 S. R. 34  East  West

App. Center - NE - 1/4 Spot Location / QQQQ County: Finney

3960' Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

1320' Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well

SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: None Set at: X Cemented with: X Sacks

Surface Casing Size: 10 3/4" - 33# Set at: 750' Cemented with: N/A Sacks

Production Casing Size: 7" - 20# Set at: 2720' Cemented with: N/A Sacks

List (ALL) Perforations and Bridgeplug Sets: 2434' - 2452', 2456' - 2478', 2502' - 2522', 2552' - 2592'

600 Total Shots

Elevation: 2936' ( G.L. /  K.B.) T.D.: 2725' PBTD: 2709' Anhydrite Depth: N/A

(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Set cast iron bridge plug at approximately 2400' inside 7" casing. Use a wireline bailor

to spot a couple of sacks of cement on top plug. Pump a mud spacer from 2400' to approximately 1500' from surface with 30 sacks of cement. Run a mud spacer to 1000' & perforate 7" casing with a

couple of holes & circulate 7" casing both inside and outside up into 10 3/4" surface pipe. Complete by hooking onto 10 3/4" surface & attempt to pump into it. Cut both 10 3/4" & 7" casing off 6' below G.L., weld cap & backfill site.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Steve Lehning

Phone: ( 620 ) 675 - 8185

Address: P.O. Box 815 City / State: Sublette, KS 67877

Plugging Contractor: Halliburton KCC License #: 5287 99997 (Contractor's)

Address: Liberal, Kansas Phone: ( 800 ) 853 - 3555

Proposed Date and Hour of Plugging (if known?): As soon as new well is tied into pipeline.

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: June 21, 2006 Authorized Operator / Agent: Steve Lehning FOR KANSAS NATURAL GAS OPERATING, INC. (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Kansas Natural Gas Operating, Inc.  
PO Box 818  
1200 Main Street  
Hays, KS 67601

June 28, 2006

Re: FINNUP #1  
API 15-055-00483-00-00  
NE 19-24S-34W, 3960 FSL 1320 FEL  
FINNEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888

Sincerely  
  
David P. Williams  
Production Supervisor