

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -163 -20,826-00-00 (of this well)

Operator's Full Name Shields Oil Producers, Inc.
Complete Address Shields Bldg., Russell, Kansas
Lease Name Schindler Well No. 1
Location SW NW NW Sec. 19 Twp. 8 Rge. (E) (W) 17
County Rooks Total Depth 3412
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 6 P Day 13 Month 7 Year 1978

The above well was plugged as follows:

RTD 3412' 8 5/8 csg set 245' cwc 180 sk. Flg. Mat. 50-50 poz 2% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.
Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1978
JUL 18, 1978
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7-18-78
INV. NO. 7681-W

Signed: Leo Massey
Well Plugging Supervisor