

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20379-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1970
CONSERVATION DIVISION
Wichita, Kansas
10-19-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name L. J. Dreiling & Sons, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Kelley Well No. 1

Location CNW-NW Sec. 1 Twp. 7 Rge. (E) (W) 23

County Graham Total Depth 3885'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 11:30 AM Day 16 Month 10 Year 1970

The above well was plugged as follows:

240'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru
DP from 1200' to 875'. Pulled DP to 250' and displaced 25 Sx. cement thru DP from
250' to 175'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 10-19-70

INV. NO. 2709-W