

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SE SW NW

SEC. 19 TWP. 8 RGE. 17W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 3 Lease _____ Schindler

Operator V. D. Sidey Oil Co Address Russell, Kans

Field _____ County Rooks

Total Depth 3414 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 106' Circulated with cement - 5 1/2" at 3410' with 100
sax cement behind.

Filled with sand to 3400', set 4 sax cement with dump bailer,
pulled 2700' 5 1/2" - pumped hole full commercial mud (30 sax)
pumped cementing plug to 165' followed by 50 sax cement -
cement 165' to 0'.

Mudding and cementing by Halliburton Cementing Co.

Edwin Lett
District Conservation Agent

Date 2-18-56

PLUGGING
FILE SEC 19 T 8 R 17W
BOOK PAGE 43 LINE 8

MAR 2 - 1956
CONSERVATION DIVISION
Wichita, Kansas