

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 118-37

LOCATION SE SE NW

SEC. 19 TWP. 8 RGE. 17

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Schindler

Operator V. D. Sidey Address Russell, Kans

Field _____ County Rooks

Total Depth 3408 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 116' circulated with cement - 5 1/2" at 3403' with
25 sax cement behind - Squeezed in Dakota with cement.
Filled with sand to 3390', set 4 sax cement with dump bailer.
pulled 460' 5 1/2" - pumped hole full mud (35 sax Gel) - pumped
cementing plug to 220', followed by 70 sax cement - Cement 220' to 0',
Mudding and cementing by Halliburton Co - 250# pump pressure.

E. J. Kelly
District Conservation Agent

Date 1-7-57

PLUGGING
FILE SEC 19 T 8 R 17E
BOOK PAGE 118 LI E 37

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1957
CONSERVATION DIVISION
Wichita, Kansas