

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SE SW NE

SEC. 19 TWP. 8 RGE. 17

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease Stamper

Operator Sidey Oil Co Address Russell, Kans

Field _____ County Rooks

Total Depth 3404 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____

(Describe briefly the manner in which the well was plugged)

8 3/8" at 103' Circulated with cement - 3 1/2' at 3395' with

100 sax cement behind. P.B. to 3281', perforated at 3158'.

Sand to 3100', set 4 sax cement with dump bailer, pulled 2700'

3 1/2' - pumped hole full mud (20 sax Gel) pumped cementing

plug to 215', followed by 70 sax cement - cement 215' to 0'.

Mudding and Cementing by Halliburton Co.

PLUGGING
FILE SEC. 19 T. 8 R. 17
BOOK PAGE 147 LINE 15

sep-6-1955

E. P. Perry
District Conservation Agent

Date 9-6-55