

DISTRICT CONSERVATION AGENT'S REPORT

[Handwritten signature]

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SE SE SW

SEC. 19 TWP. 8 RGE. 17

Dry Hole lost hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Krug

Operator D. G. Hansen Address e/o C & G Drg Co Wichita, Kans

Field _____ County Rooks

Total Depth 3135 Feet.

Plugging Contractor C & G Drg Co

Plugging Contractor's License No. _____

Address _____
(Describe Briefly the manner in which the well was plugged)

8 5/8" at 176' circulated with cement.

Bottom Jt. 8 5/8" knocked off while fishing - top of Jt. at 680'.

Gunned pits, circulated hole with heavy mud, set cementing plug at
550', displaced 20 sax cement through drill pipe at 550', heavy mud
to 150', set cementing plug, 1/2 sack hulls and 15 sax cement, heavy
mud to 40', set cementing plug, 1/2 sack hulls and 10 sax cement to
bottom cellar.

Gilbert Leiker

By *[Signature]*

District Conservation Agent

RECEIVED
STATE CORPORATION COMMISSION
DEC 19, 1957
DEC 19 1957

Date 12-16-57

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 19 T 8 R 17
BOOK PAGE 70 LINE 34