

15-123-19003-00-00

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

OR


FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
off formations.

Mitchell County, Sec. 26 Twp. 8 S Rge. 10 W (E) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines
Lease Owner **Olson Drilling Company**
Lease Name **Palen** Well No. **1**
Office Address **Box 2680, Tulsa, Oklahoma**
Character of Well (completed as Oil, Gas or Dry Hole) **Dry**
Date well completed **11-30-46** 19
Application for plugging filed **12-1-46** 19
Application for plugging approved **12-1-46** 19
Plugging commenced **12-1-46** 19
Plugging completed **12-1-46** 19
Reason for abandonment of well or producing formation **Dry hole**

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? **Yes**

Name of Conservation Agent who supervised plugging of this well **Mr. Durkee**
Producing formation Depth to top Bottom Total Depth of Well **4202** Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Lansing		2940		8-5/8"	242	---
Mississippi		3599				
Viola		3852				
Arbuckle		4146				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole bridged at 230', plugged w/15 sx cement

Hole bridged at 10' and cemented to top of surface pipe with 5 sx.

26 8 10W
85 1

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to **Olson Drilling Company**
Address **Box 2680, Tulsa, Oklahoma**

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
J. B. Hoover (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Notary Public seal for Walter, 1946, Tulsa, Oklahoma. Includes handwritten address Box 2680 Tulsa, Okla and date December 10, 1946.

SUBSCRIBED AND SWORN to before me this 9th day of December, 1946

My commission expires Mar. 26, 1949



12-10-46

OLSON DRILLING COMPANY

TULSA, OKLAHOMA

WELL LOG

15-123-19003-00-00

OPERATOR Olson Drilling Company
 WELL Palen #1
 LOCATION NW SW SE Section 26-8S-10W
 Mitchell County, Kansas


DATE COMMENCED 10-23-46

DATE COMPLETED 12-1-46

3M244

DEPTH FORMATION DEPTH FORMATION

0 -	103	Shale	2980 -	3371	Lime
	285	Shale & gyp		3478	Shale, lime streaks
		8-5/8" Casing at 242'		3546	Shale & lime
		w/2 1/2 Sx		3580	Shale
	295	Shale		3599	Sand
	475	Shale & shells		3620	Chert & lime
	540	Shale & sand		3628	Chert
	820	Shale & shells		3674	Chert & lime
	930	Red shale		3727	Lime, shale streaks
	1247	Shale		3818	Lime
	1345	Shale & shells		3845	Shale
	1507	Anhydrite, shale streaks		3869	Dolomite
	1610	Red shale		4140	Lime
	1635	Lime		4150	Shale
	1720	Shale, lime streaks		4205	Lime T.D.
	1730	Anhydrite			
	1757	Shale, lime streaks			
	1790	Shale			
	1816	Chert & lime			
	1975	Shale			
	2025	Sandy lime			
	2148	Shale & lime			
	2425	Shale			
	2445	Lime			
	2475	Shale, lime streaks			
	2485	Lime			
	2692	Shale & lime			
	2745	Shale, lime streaks			
	2775	Lime			
	2801	Lime, shale streaks			
	2861	Lime			
	2897	Lime & shale			
	2980	Shale, lime streaks			



12-10-46

26 8-10W
85 7

I HEREBY CERTIFY THAT THE ABOVE IS A TRUE AND CORRECT COPY OF THE LOG OF THE ABOVE DESCRIBED WELL.

[Signature]