

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-141-203360000

LEASE NAME Bader

WELL NUMBER 1

2,310 Ft. from <sup>N</sup> Section Line

330 Ft. from E Section Line

SEC. 25 TWP. 8 RGE. 12 (E) or (W)

COUNTY Osborne

Date Well Completed 5-18-97

Plugging Commenced 5-18-97

Plugging Completed 5-19-97

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Brungardt Oil & Leasing Co.

ADDRESS PO Box 871, Russell, Kansas 67665

PHONE#(913) 483-4975 OPERATORS LICENSE NO. 3956

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-18-97 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No if not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3,250'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	206'	Cmtd. w/140 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Push bridge plug to 810', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 635', pump 90 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Shields Bldg., Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brungardt Oil & Leasing Co.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman

Contractor

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec - Treas

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 27th day of May, 19 97

Ruth Phillips  
Notary Public

My Commission Expires:






Shields 15-141-20336-00-00

Russell, Kansas

WELL LOG

Operator: Brungardt Oil & Leasing Co.  
Well: Bader #1  
Commenced: May 12, 1997  
Completed: May 19, 1997  
Contractor: Shields Drilling Co.

Well Description: SE SE NE  
Sec. 25-8S-12W  
Osborne Co., Kansas



Elevation: 1,686' KB

Treatment:

Production: D & A

Tops:

CASING RECORD

Size	Run	Pulled
8 5/8"	206'	Cmtd. 140 sax

..... Figures Indicate Bottom of Formations .....

Shale & sand	790'	
Anhydrite	823'	
Shale	2,160'	
Shale & lime	2,915'	
Lime	3,250'	RTD

RECEIVED  
KANSAS COMMISSION  
MAY 28 A 1:54