

API NUMBER 15-141-203390000

LEASE NAME Bonnie Thompson

WELL NUMBER 1

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 35 TWP. 8 RGE. 12 (E) or (W)

COUNTY Osborne

Date Well Completed 9-19-97

Plugging Commenced 9-19-97

Plugging Completed 9-19-97

(date)

LEASE OPERATOR Brungardt Oil & Leasing Co.

ADDRESS PO Box 871, Russell, KS. 67665

PHONE#(913) 483-4975 OPERATORS LICENSE NO. 3956

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-19-97

by Marvin Miller

(KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,320'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	216'	Cmtd. w/140 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. Push bridge plug to 900', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 730', pump 100 sax cement on plug thru drill pipe. Push bridge plug to 265', pump 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brungardt Oil & Leasing Co.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman Contractor

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Jr. - Trust

(Address) Shields Bldg. PO Box 709, Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 30th day of September, 19 97

Lucretia Phillips
 Notary Public

My Commission Expires: _____





Shields


15-141-20339-00-00

Russell, Kansas

WELL LOG

Operator: Brungardt Oil & Leasing Co.
 Well: Bonnie Thompson #1
 Commenced: September 12, 1997
 Completed: September 19, 1997
 Contractor: Shields Drilling Co.

Well Description: SE SE SE
 Sec. 35-8S-12W
 Osborne Co., Kansas



Elevation: 1,779' KB

Treatment:

Production: D & A

Tops:

CASING RECORD

Size	Run	Pulled
8 5/8"	216'	Cmtd. w/140 sax

..... Figures Indicate Bottom of Formations

Surface soil, rock & shale	115'	
Shale	219'	
Sand & shale	680'	
Shale	888'	
Anhydrite	925'	
Shale	2,266'	
Shale & lime	2,990'	
Lime	3,320'	RTD

15-141-20339-00-00
 RECEIVED
 OIL & GAS
 DEPARTMENT
 OCT 2 11 58 AM '97