


15-141-20034-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Osborne County. Sec. 19 Twp. 8S Rge. 13 E/W
Location as "NE/CNW\SW $\frac{1}{4}$ " or footage from lines
SW NW NW
Lease Owner Petroleum Management Inc.
Lease Name Roadhouse Well No. #2
Office Address 400 N Woodlawn, Suite 201 Wichita, KS. 67208
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed November 21, 1978
Application for plugging filed November 21, 1978
Application for plugging approved November 21, 1978
Plugging commenced November 8, 1978
Plugging completed November 21, 1978
Reason for abandonment of well or producing formation
no commercial production

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? * Yes

Name of Conservation Agent who supervised plugging of this well * Duane L. Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface casing	common	0	213'	8 5/8"	213'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug #1@ 550' with 70 sxs
Plug #2@ 215' with 120 sxs
Plug #3@ 40' with 15 sxs hulls & 10 sxs cement 50-50 poz 2% gel

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pioneer Drilling Company, Inc. 11-30-78
308 West Mill Plainville, Kansas 67663

*
STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Dale Silcott (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) By: Dale Silcott
Petroleum Management, Inc.
400 N. Woodlawn, Suite 201, Wichita, Ks. 67208
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of November, 1978

My commission expires



Bonnie Brown
Bonnie Brown - Notary Public.

15-141-20094-00-00

WELL LOG

OPERATOR: Petroleum Management Inc. (PMI)

WELL NAME: Roadhouse #2

LOCATION: SW NW NW 19-8S-13W

COUNTY: Osborne

STATE: Kansas

WELL COMMENCED: November 8, 1978

WELL COMPLETED: November 21, 1978

ELEVATION: 2070' KB

TOTAL DEPTH: 2755'

PRODUCTION: Dry Hole

RIG NO: #2

CASING - 8-5/8": 213' of 28# cemented with 115 sxs common 2% gel 3% cc

5-1/2": none

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0'	15'			
15'	221'		221' - 1 degree	
221'	683'			
683'	683'	shale and sand		
683'	900'	shale		
900'	1120'	shale		
1114'	1503'	shale and sand	1114' - 1 degree	
1503'	1845'	shale and lime		
1845'	2013'	shale and lime		
2013'	2195'	shale and lime		
2195'	2264'	shale and lime		
2264'	2264'	shale and lime		
2264'	2334'	shale and lime		
2334'	2525'	shale and lime		
2525'	2656'			
2656'	2755'	shale and lime		
2755'	RTD			

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1978

CONSERVATION DIVISION
Wichita, Kansas

11-30-78

STATE OF KANSAS
COUNTY OF

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct

PIONEER DRILLING CO., INC.

By

Charles R. ...

SUBSCRIBED AND SWORN TO, BEFORE ME, This 27th day of Nov., 1978.

MY COMM. EXP. SEPT. 6, 1981.

Krystal Schwenn
KRYSTAL SCHWENN - NOTARY PUBLIC

