

15-065-20498-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1971
CONSERVATION DIVISION
Wichita, Kansas
11/15/71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cecil M. Keller and Edmiston Oil Company,
Complete Address 801 First National Bank Building, Wichita, Kansas.
Lease Name Trexler Well No. 1
Location NW-SW-SE Sec. 14 Twp. 7 Rge. (E) (W) 23
County Graham Total Depth 3825'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor E. K. Edmiston Drilling Company, Incorporated,
Address 801 First National Bank Building, Wichita, Ks. License No.
Operation Completed: Hour 8:30 AM Day 13 Month 11 Year 1971

The above well was plugged as follows:

217'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 875'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 100 Sx. cement thru
DP from 1100' to 775', Pulled DP to 245' and displaced 25 Sx. cement thru DP from
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 11-15-71
INV. NO. 4653-W