

State of Kansas



15-065-20107-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 7 1967

12-7-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Lowell Moore of C and G Drilling Company has this date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: Halliburton Oil Producing Company,

Complete Address: 520 Cameron Building, Oklahoma City, Oklahoma.

Lease Name: H. A. Moore Well No. 1

Location: NE-NE-SE Sec. 26 Twp. 7 Rge. (E)(W) 25

County Graham Total Depth 3940' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Moore was instructed to plug the well as follows:

274'--8 5/8" Surface casing, cement circulated with 200 Sx.
Dakota section from 990' to 1175'.

Circulate hole with heavy mud. Pull DP to 1200' and displace 100 Sx.
cement thru DP. Pull DP to 300' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent