



15-065-21666-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Jack Oston of Kissinger Drilling Co. has this

date requested permission to plug the following described well:

Operator's Full Name: Kissinger Drilling Co.

Complete Address: Suite 850-410 17th St., Denver, Co. 80202

Lease Name: Keith Well No. 13-C-24

Location: SW SW SW Sec. 24 Twp. 7 Rge. 25 (E) (W)

County: Graham Total Depth: 3980'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereafter indicated: _____

Mr. Oston was instructed to plug the well as follows:

8 5/8"-255' S.P. cuc.w/175 sacks common-2% Gel.-3% Cal.Cl.

Ordered 150 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 1200' w/80 sacks cement

2nd plug @ 260' w/40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement.

Circulate 10 sacks in rat hole & 10 sacks in mouse hole

Very truly yours,

[Signature]
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
AUG 02 1982
CONSERVATION DIVISION
Wichita, Kansas

8-2-82