



15-065-20498-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS, 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
NOV 15 1971
CONSERVATION DIVISION
Wichita, Kansas

11/15/71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. L. C. Brau of E. K. Edmiston Drlg. Co., Inc. has this date requested permission to plug the following described well:

Mr. Brau guarantees payment of the plugging fee.

Operator's full Name: Cecil M. Keller & Edmiston Oil Company,

Complete Address: 801 First National Bank Building, Wichita, Kansas.

Lease Name: Trexler Well No. 1

Location: NW-SW-SE Sec. 14 Twp. 7 Rge. (E)(W) 23

County: Graham Total Depth 3825' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Brau was instructed to plug the well as follows:

217'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 875'.

Circulate hole with heavy mud. Pull DP to 1100' and displace 100 Sx.
cement thru DP. Pull DP to 245' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent