

6 031560

6-28

00-00 88P

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 065-20,635  
C SE NW, SEC. 34, T 7 S, R 23 (W)

TECHNICIAN'S PLUGGING REPORT

3300 feet from S section line  
3300 feet from E section line

Operator License # 7802

Lease Name Dawson Well # 1

Operator: Rider Oil & Gas Exploration  
Name & Address: 2805 Bentbay Circle  
Wichita, Kansas 67204

County Graham 124.83

Well Total Depth 3841 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 195'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cement Company License Number \_\_\_\_\_

Address Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 28 Month: 6 Year: 19 91

Plugging proposal received from Don Rider

(company name) Rider (phone) \_\_\_\_\_

were: 8 5/8" set @ 195' w/200 sx. 5 1/2" set @ 3839' w/200 sx. PBSD 3807'.

Perf. 3738' - 76'. Order 350 sx. 65/35 poz. - 10% gel. - 800# hulls.

Allied Cement Company - Nutting Water Trucks.

5 1/2 open to perf. Shot holes @ 1980' and 1220'.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:00 P.M. Day: 28 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT Squeezed 5 1/2 w/275 sx. cement blend w/500# hulls mixed in to

max. P.S.I. 500#. Close in 200#. Squeezed 8 5/8 w/75 sx. cement blend w/300# hulls.

Mixed in to max P.S.I. 500#. Close in 200#. Plug complete.

RECEIVED STATE CORPORATION COMMISSION

III 22 1991

CONSERVATION DIVISION Wichita, Kansas

Remarks: \_\_\_\_\_ (If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.)

DATE 8-6-91 INV. NO. 32575

Signed Carl Goodrow (TECHNICIAN)