

4-031870

10-13

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-01 ³⁰⁷1952-00-00

C SE NW /4 SEC. 35, 07 S, 23 W
3300 feet from S section line
3300 feet from E section line

Operator license# 4656

Lease Wanker well #X-1

Operator: Davis Petroleum, Inc.

County Graham

Address: R.R. 1 - Box 183B
Great Bend, Kansas 67530

Well total depth 3775 feet - 122.68
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 195 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 13 Month: October Year: 93

Plugging proposal received from: L.D. Davis

Company: Davis Petroleum, Inc. Phone:

Were: Order 300 sxs. 65/35 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 2:15 P.M., Day: 13, Month: October, Year: 93

Actual plugging report: 8 5/8" set @ 195' with NA cwc. 4 1/2" set @ 3772' w/NA. Prod. PF. 3698' - 3734'. Squeezed 4 1/2" w/200 sxs. cement blend w/400# hulls mixed in to Max. P.S.I. 300#. Close in P.S.I. 100#. Squeezed 8 5/8" w/100 sxs. cement blend w/100# hulls mixed in to Max. P.S.I. 300#. Close in P.S.I. 100#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X. Elevation: GL

I did not observe the plugging.

Carl Goodrow

(agent)

INVOICED
DATE 11-8-93
INV. NO. 39164

Form CP-2/3

RECEIVED
STATE CORPORATION COM
NOV 05 1993
11/5/93
CONSERVATION DIVISION
Wichita, Kansas