

6 030409

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-181-20,207-00-00  
C.S.W.N.E. SEC. 14, T. 7 S, R. 37 W

TECHNICIAN'S PLUGGING REPORT

\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

Operator License # 5219

Lease Name Sramek Well # 1

Operator: Kimbark Oil & Gas Co.  
Name & Address: 1500 Lincoln St. # 700  
Denver Colorado  
80203

County Sherman 163.87  
Well Total Depth 5042 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 563'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Okmar Oil & Gas Co. License Number 5219

Address as above

Company to plug at: Hour: AM Day: 29 Month: 3 Year: 19 85

Plugging proposal received from Gary Bridgwell

(company name) Kimbark (phone) \_\_\_\_\_

were: 8 5/8" set @ 563' w/ 400# cement 5 1/2" set @ 5042' w/ 200#  
Perfs from 4866' to 4969' ordered 300# 50/50 pg 6 1/2" 3" 5 1/2"  
W.P. 50# pg 6 1/2" 3" 5 1/2" shells. Halliburton Cement  
well water trucks.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:PM Day: 29 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT Pump down 5 1/2" w/ 5# shells 50# cement 27# gel  
25# cement pump pressure 1250<sup>+</sup> shut in at 1000<sup>+</sup> pumped on  
back side 5 1/2" - 8 3/8" annulus 3# shells 11# gel 6# cement  
max press 450<sup>+</sup> shut in at 150<sup>+</sup> let both sides stand awhile  
then bleed off for welder to cut off pipe. fluid stayed at  
surface of pipes. Plug Complete.

Remarks: \_\_\_\_\_

(If additional description is necessary, use BACK of this form.)

INVOICED RECEIVED  
I (did, did not) observe this plugging. STATE CORPORATION COMMISSION

DATE 4-9-85

Signed Carl Goodrow (TECHNICIAN) 4-3-85

WELL NO. 7652

APR 05 1985  
MAY 09 1985  
CONSERVATION DIVISION  
Wichita, Kansas