

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-19048-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 31-8S-16W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: BOLLER B Well Number: 1
County: ROOKS Total Vertical Depth: 3360 feet

Operator License No.: 32247 Conductor Pipe: Size feet: 109.20
Op Name: CRAWFORD, JEFF DBA JEFF'S OILWELL Surface Casing: Size 8.625 feet: 160 w/140 sxs cmt
Address: BOX 245 705 BAUM AVE. Production: Size 4.5 feet: 3356
NATOMA, KS 67651 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/09/2002 10:00 AM
Plug Co. License No.: 32247 Plug Co. Name: CRAWFORD, JEFF DBA JEFF'S OILWELL SUPERVISION
Proposal Rcvd. from: JEFF CRAWFORD Company: CRAWFORD, JEFF DBA JEFF'S OIL Phone: (785) 885-4655

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/09/2002 12:45 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Tubing stuck in hole.
Perforated tubing/casing at 750' and 1000'.
Tied onto tubing and circulated with 60 sxs 60/40 pozmix - 10% gel cement.
Shut in backside and pumped 95 sxs cement.
Max. P.S.I. 700#. S.I.P. 500#.
Pressured backside to 300# and blew out casing.
Lots of old cement present in cellar.
Well probably had been squeezed.

RECEIVED
NOV 14 2002 11/14/02
KCC

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Case Morris
(TECHNICIAN)

10

INVOICED Form CP-2/3

DATE 11-15-02

INV. NO. 2003060816

NOV 06 2002