

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01326-00-00  
Spot: SWNWSW Sec/Twnshp/Rge: 31-8S-16W  
1650 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: BOLLER A Well Number: 2  
County: ROOKS Total Vertical Depth: 3451 feet

Operator License No.: 8735

Conductor Pipe: Size feet: 8 1/2.16

Op Name: CRAWFORD, STEPHEN G. DBA S & M OI

Surface Casing: Size 8.625 feet: 178 140 SX CMT

Address: 1725 250TH AVE.  
HAYS, KS 67601

Production: Size 4.5 feet: 3451 200 SX CMT

Liner: Size feet:

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/05/2002 8:00 AM

Plug Co. License No.: 8735

Plug Co. Name: CRAWFORD, STEPHEN G. DBA S & M OIL

Proposal Rcvd. from: STEVE CRAWFORD

Company: CRAWFORD, STEPHEN G. DBA S & M OIL Phone: (785) 650-4003

Proposed Plugging Method: Ordered 175 sxs 60/40 pozmix - 10% gel - 500# hulls.  
D.V. at anhydrite - cement visible at surface in 8 5/8" S.P.  
WHM - 1877'.

Plugging Proposal Received By: DENNIS HAMEL

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 08/05/2002 11:00 AM

KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.I.H. with tubing to 1270'.  
R.U. Cementers spotted 80 sxs cement and 400# hulls to circulate at surface.  
POOH with tubing. Squeezed 4 1/2" casing with 50 sxs cement.  
Max. P.S.I. 500#. S.I.P. 200#.  
8 5/8" S.P. - cement visible at surface.

RECEIVED

AUG 16 2002

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 8-19-02

INV. NO. 2003060237

AUG 07 2002