

7-14  
4-031724

212  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

E-24,567  
API number: 15-065-22324-00-00

NW NW NW NW /4 SEC. 35, 07 S, 23 W  
5180 feet from S section line  
5160 feet from E section line

Operator license# 4656

Lease Korb well # 2Inj

Operator: Davis Petroleum, Inc.

County Graham

Address: R.R. 1  
Box 138B  
Great Bend, Kansas 67530

Well total depth 3842 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 305 feet

124.86

Aband. oil well     , Gas well     , <sup>ENHR</sup> Input well X, SWD     , D & A     

Plugging contractor: Halliburton License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 14 Month: July Year: 92

Plugging proposal received from: L. D. Davis

Company: Davis Petroleum, Inc. Phone:                     

Were: Order 225 sx. 65/35 pozmix - 8% gel. - 500# hulls.  
Alt. II Completion.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[      ], Part[ X ], None[      ]

Completed: Hour: 6:30P.M., Day: 14, Month: July, Year: 92

Actual plugging report: 8 5/8" set @ 305' w/200 sx. cwc. 4 1/2" set @ 3840' w/150 sx. Perf. @ anhy. cwc. to surface. Perf. 3741' - 54'. P.B.T.D. 3784'. Ran tubing to 2200' circulated cement to surface w/125 sx. cement blend w/300# hulls mixed in. Laid down tubing squeezed 4 1/2" to 500# Max. P.S.I. Pressure locked up. Squeezed 8 5/8" with 2 BBL. slurry to 300# P.S.I. Cement at surface.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 29 1992

CONSERVATION DIVISION  
Wichita, Kansas

Remarks:

Condition of casing(in hole): GOOD X BAD      Anhy. plug: YES X NO       
Bottom plug(in place): YES X, CALC     , NO      Dakota plug: YES X, NO       
Plugged through TUBING     , CASING X. Elevation:              GL     

7/29/92

I did[ X ] / did not[      ] observe the plugging.

Carl Goodrow

DATE 8-6-92

REV. NO. 35880

(agent)