

4
050016

11-28

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-20,482 -00-00
NW SW NW, SEC. 34, T 8 S, R 17

TECHNICIAN'S PLUGGING REPORT

Operator License # 5097
Operator: Martin Oil Co.
Name & Address: 150 N. Main #1010
Wichita, Ks. 67202
316-264-0352

3630 feet from S section line
4950 feet from E section line

Lease Name McMullen Well # A-1
County Rooks 112.39

Well Total Depth 3458 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 207

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Martin Oil Co. License Number 5097
Address

Company to plug at: Hour: 8:30 AM Day: 28 Month: Nov Year: 19 89

Plugging proposal received from Williams Stockstill

(company name) Martin Oil Co. (phone)

were: Order 275 sks 60/40 poz 6% gel w/500 lbs. hulls.

Well record: 8 5/8" s.p. set at 207' w/200 sks. 5 1/2" casing set at 3451' w/200 sks D.v. set at 1341' w/300 sks. Perfs at 3236 -38. Pump cement down 5 1/2" casing fill to surface shut in under pressure. Pump cement down backside fill to surface. Shut in under pressure.

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:15 AM Day: 28 Month: Nov Year: 19 89

ACTUAL PLUGGING REPORT Ran wireline to 3000' Tied onto backside pumped 12 sks 60/40 poz

6% gel. Shut in w/400 psi. Pumped down 5 1/2" casing 50 sks 60/40 poz 6% gel starting mixing

hulls and pumped 213 sks cement and 500 lbs. hulls. Max psi 350 shut in psi 100. November

11, 1989 Halliburton ran wireline to check cement top down 722'. Dumped 4 yds. Ready mix

down 5 1/2" casing filled to surface.

Remarks: (If additional description is necessary, use BACK of this form)

I did not observe this plugging.

DATE 2 JAN 24 1990

INV. NO. 27131

Signed Marwin Miller (TECHNICIAN)
Marvin Miller

RECEIVED STATE CORPORATION COMMISSION

JAN 17 1990 11/17/90

CONSERVATION DIVISION Wichita, Kansas