

6 041247

12-19 15-163-01335-20-20

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION NE NW  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 4-23-48

SEC. 3 3 T 8 S, R 16 W/E  
4950 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Bergier (Graves) Well # 1

Operator: Murfin Drilling co.

County Rooks 111.44

Name & Address 250 N. Water

Well Total Depth 3429 feet

Suite 300

Conductor Pipe: Size feet

Wichita, Ks. 67202

Surface Casing: Size 8 5/8 feet

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cementing License Number

Address Hays, Ks.

Company to plug at: Hour: 9:00 AM Day: 19 Month: Dec. Year: 19 90

Plugging proposal received from John Gertschner

(company name) Murfin Drilling (phone)

were: 5 1/2 casing set at 3428 w/NA sks cement: perfs at 3087. to 3302:

Perf anhy at 1258; perf base dakota at 750; Sq dakota w/235 sks cement.

Ordered 400 sks 65/35 poz 10% gel w/1/4 lb f.c. plus 500 lbs. hulls.

Plugging Proposal Received by Dennis Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:00PM Day: 19 Month: Dec. Year: 19 90

ACTUAL PLUGGING REPORT Pumped in 5 1/2 casing w/25 sks cement w/1/4 lb f.c. plus pumped

in add 300 sks cement w/1/4 lb f.c. and 400 lbs. hulls mixed in cement. Max 1000 lbs.

SI 750 lbs. Pumped in 8 5/8 casing w/75 sks cement w/1/4 lb f.c. and 100 lbs.

hulls mixed in cement. Max 750 lbs. S.I. 500 lbs.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 17 1991

INV. NO. 30513

Sub-S

Signed Dennis L. Hamel  
(TECHNICIAN)  
Dennis L. Hamel