

2-17

4-041883

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-20,786 00-00

C NW NE /4 SEC. 33, 08 S, 16 W
4620 feet from S section line
1980 feet from E section line

Operator license# 6569

Lease: Adams "A" Well # 2

Operator: Carmen Schmidt, Inc.

County: Rooks 109.52

Address: P.O. Box 47
Great Bend, Kansas 67530

Well total depth 3370 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 212 feet
w/ 150 sxs.cmt.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 12:30 P.M Day: 17 Month: February Year 1997

Plugging proposal received from: Curtis Hitchman

Company: Carmen Schmidt, Inc. Phone: 2/20/97

Were: 4 1/2" casing set at 3369' w/125 sxs.
Ordered 200 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perfs. at 3050' - 3287'. Anhy. at 1240'. Casing parted at 780'.

Emergency permission To plug w Alg over hole. H Danes

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 3:30 P.M., Day: 17, Month: February, Year: 1997

Actual plugging report: R.I.H. with tubing to 3000'. Spotted 100 sxs cement with 300# hulls. Pulled to 1500'. Spotted 50 sxs with 200# hulls to circulate at surface. P.O.O.H. with tubing and squeezed casing with 25 sxs cement. Max. P.S.I. 500#. S.I.P. 200#. 8 5/8" S.P. - Squeezed 25 sxs cement. Max. P.S.I. 200#. S.I.P. 75#.

Remarks:
Condition of casing(in hole): GOOD BAD X
Bottom plug(in place): YES X, CALC , NO
Plugged through TUBING X, CASING .
Anhy.plug: YES X NO
Dakota plug: YES X, NO
Elevation:

RECEIVED
KANSAS CORP COM
1997 FEB 20 P 1:23

INVOICED
DATE FEB 21 1997

INV. NO. 47651
2-17 APR 25 1997

Herb Deines
(agent)