

Harry

6 031372

6-12

NOC

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-20100-00-00

NE SE NW SEC. 33 T. 8 S. R. 16 W/E

3630 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
6033

Operator License # \_\_\_\_\_

Lease Name Bergier Well # 1 W

Operator: Murfin Drilling Co.

County Rooks 109.36

Name & Address 250 N. Water Suite 300

Well Total Depth 3365 feet

Wichita, Ks. 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 190

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well vxx SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated Docket Number E-13043, Canceled. app to add well to docket

Plugging Contractor Halliburton License Number \_\_\_\_\_

Address Hays, Ks.

Company to plug at: Hour: AM Day: 12 Month: June Year: 19 90

Plugging proposal received from John

(company name) Murfin (phone) \_\_\_\_\_

were: 8 5/8 set 190 cwc. 4 1/2 set at 3364 w/200 sks. PRTD 3281

Perfs 3116-3277. Order 400 sks 65/35 poz

8% gel 500 lbs. hulls. Halliburton Cement Co. Murfin Water Trucks.

Shots at 1258 and 825.

Pulled production equipment out of hole. Hole open thru perfs

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None xx

Operations Completed: Hour: 10:30AM Day: 12 Month: June Year: 19 90

ACTUAL PLUGGING REPORT Sq 4 1/2 casing w/250 sks cement blend

w/400 lbs. hulls mixed into max psi 1000 lbs. Close in psi 250 lbs.

Sq 8 5/8 w/50 sks cement blend w/100 lbs. hulls mixed into max psi 500 lbs.

Close in psi 400 lbs. Plug complete.

Remarks: \_\_\_\_\_

**INVOICED**

(If additional description is necessary, use BACK of this form.)

I (xxx) did not observe this plugging.

DATE 7-24-90

INV. NO. 28723

*Handwritten initials*

Signed Carl Goodrow  
(TECHNICIAN)

Carl Goodrow

