

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
 K.A.R. 82-3-117

Form CP-4
 December 2003
 Type or Print on this Form
 Form must be Signed
 All blanks must be Filled

Lease Operator: CATTLEMAN'S OIL OPERATIONS
 Address: 2260 Catherine Road Hays, KS 67601
 Phone: (785) 625-5394 Operator License #: 7064
 Type of Well: D & A Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 6/17/06 (Date)
 by: Bruce Bayse (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
None Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 051-25,526-00-00
 Lease Name: KRAUS "B"
 Well Number: 4
 Spot Location (QQQQ): 16' N - SW - NW - SE
1660 Feet from North / South Section Line
2310 Feet from East / West Section Line
 Sec. 20 Twp. 14 S. R. 19W East West
 County: Ellis
 Date Well Completed: 6/18/06
 Plugging Commenced: 4:15AM 6/18/06
 Plugging Completed: 7:00AM 6/18/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	211	10 3/4	210.99	None


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug @ 1510'W/25sks 15sks In Rat Hole Circulated 1st Plug 15 Minutes W/55Vis Mud
 2nd Plug @ 765'W/100sks Plugs displaced with mud.
 3rd Plug @ 265'W/40sks Total 190sks 60/40Poz 6%Gel W/1/4#CF/sk By Allied Cementing
 4th Plug @ 40'W/10sks Completed @ 7:00AM 6/18/06

Name of Plugging Contractor: Discovery Drilling Co., Inc. License #: 31548
 Address: P.O. Box 763 Hays, KS 67601
 Name of Party Responsible for Plugging Fees: CATTLEMAN'S OIL OPERATIONS
 State of Kansas County, Ellis, ss.

Leo Dorzweiler owner (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Leo Dorzweiler
 (Address) 2260 Catherine Rd. Hays, Kansas 67601
 _____ and SWORN TO before me this 30th day of June, 2006
Viola Dorzweiler My Commission Expires: 4-20-07
 Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
JUL 05 2006
KCC WICHITA