

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-131-20181-00-00
Spot: SWNESESW Sec/Twnshp/Rge: 12-3S-14E
810 feet from S Section Line, 3150 feet from E Section Line
Lease Name: RENYER Well #: 14-12
County: NEMAHA Total Vertical Depth: 2720 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2703	1078	195 SX CMT
SURF	8.625	282		112 SX CMT

\$ 88.40

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/10/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 2657' TO 2525' CEMENT FROM 2525' TO 2268' GEL FROM 2268' TO 300' CEMENT FROM 300' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: NONE
Date/Time Plugging Completed: 01/12/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

On 1-10-06 ran tubing and tagged bottom at 2598', spotted 2 barrels of gel from 2598' to 2525'. Pulled tubing to 2525' and pumped 45 barrels of gel and 35 sacks of cement with 1 sack of cottonseed hulls. Had cement from 2525' to 2219' and gel from 2219' to 300'. Returned to the well on 1-12-06 and shot the casing at 1078', moved up to 297' and circulated 85 sacks of cement to surface and pulled the casing.

Perfs:

Top	Bot	Thru	Comments
2473	2475		
2405	2407		
2388	2389		
2374	2376		
2330	2332		
2318	2320		

RECEIVED
KCC DISTRICT #3

JUN 27 2006 TCH

CHANUTE, KS

Remarks:

Plugged through:

RECEIVED
DATE 7-6-06
2007060017

District: 03

Signed Taylor C. Herman
(TECHNICIAN)

RECEIVED
JUL 05 2006
KCC WICHITA

PACT