

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-131-20179-00-00  
Spot: NWSESENW Sec/Twnshp/Rge: 12-3S-14E  
3150 feet from S Section Line, 3150 feet from E Section Line  
Lease Name: SCOBY Well #: 6-12  
County: NEMAHA Total Vertical Depth: 2730 feet

Operator License No.: 33233  
Op Name: HEARTLAND OIL & GAS, INC.  
Address: 1610 INDUSTRIAL PARK DRIVE  
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2719	927	205 SX CMT
SURF	8.625	260		138 SX CMT

\$ 88.73

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/16/2006 8:00 AM  
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.  
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 2675' TO 2602' CEMENT FROM 2602' TO 2278' GEL FROM 2278' TO 300' CEMENT FROM 300' TO SURFAC.E

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/18/2006 5:00 PM KCC Agent: TAYLOR HERMAN

**Actual Plugging Report:**

On 1-16-06 ran tubing and tagged bottom at 2648' and spotted 1 barrel of gel. Pulled the tubing to 2605' and pumped 45 barrels of gel and 40 sacks of cement with 1 sack of cottonseed hulls. Had cement from 2605' to 2255' and gel from 2255' to 300'. Returned to the well on 1-18-06 and shot the casing at 927' and moved up to 299', circulated 90 sacks of cement to surface and pulled the casing.

**Perfs:**

Top	Bot	Thru	Comments
2551	2552		
2453	2455		
2392	2394		
2376	2377		
2364	2366		
2328	2330		

RECEIVED  
KCC DISTRICT #3  
JUN 27 2006 TCH  
CHANUTE, KS

INVOICED  
7-6-06  
2007060017

Remarks:

Plugged through:

District: 03

Signed Taylor C. Herman  
(TECHNICIAN)

RECEIVED  
JUL 05 2006  
KCC WICHITA

PCT