

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-085-20076-00-00  
Spot: S2S2SWNW Sec/Twnshp/Rge: 14-5S-15E  
2790 feet from S Section Line, 710 feet from W Section Line  
Lease Name: ATWATER FARMS Well #: 5-14  
County: JACKSON Total Vertical Depth: 3636 feet

Operator License No.: 33233  
Op Name: HEARTLAND OIL & GAS, INC.  
Address: 1610 INDUSTRIAL PARK DRIVE  
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3521	918	330 SX CMT
SURF	8.625	237		120 SX CMT
T1	2.875	3478		

\$ 118.17

Well Type: SWD UIC Docket No: D28351.0 Date/Time to Plug: 01/31/2006 8:00 AM  
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.  
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: CMT FROM 3636' TO 3471', GEL FROM 3471' TO 250', CMT FROM 250' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE  
Date/Time Plugging Completed: 02/01/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

On 1-31-06 ran the tubing and tagged bottom at 3600'. Pumped 80 barrels of gel and hole would not load. Pumped 50 sacks of cement with 2 sacks of cottonseed hulls. Had cement from 3600' to 3372'. Pulled tubing to 3250' and loaded the hole with 20 barrels. Ran tubing to 3350' and pumped 73 barrels of gel, had gel from 3350' to 300'. Returned to the well on 2-01-06 and shot the casing at 918', moved up to 310' and circulated 90 sacks of cement to surface and pulled the casing.

RECEIVED  
KCC DISTRICT #3  
JUN 27 2006 TCH  
CHANUTE, KS

Perfs:

Top	Bot	Thru	Comments
3521	3636		

INVOICED  
DATE 7-6-06  
2007060017

Remarks:

Plugged through:

District: 03

Signed Taylor C Herman  
(TECHNICIAN)

RECEIVED  
JUL 05 2006  
KCC WICHITA