

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-085-20074-00-00  
Spot: SWNESWSE Sec/Twnshp/Rge: 15-5S-15E  
810 feet from S Section Line, 1830 feet from E Section Line  
Lease Name: AMON Well #: 15-15  
County: JACKSON Total Vertical Depth: 2412 feet

Operator License No.: 33233  
Op Name: HEARTLAND OIL & GAS, INC.  
Address: 1610 INDUSTRIAL PARK DRIVE  
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2377	1022	175 SX CMT
SURF	8.625	250		120 SX CMT

\$ 78.39

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/23/2006 8:00 AM  
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.  
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 2326' TO 2250', CMT FROM 2250' TO 1825', GEL FROM 1825' TO 250', CMT FROM 250' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/25/2006 5:00 PM KCC Agent: TAYLOR HERMAN

**Actual Plugging Report:**

On 1-23-06 ran tubing and tagged bottom at 2277'. Pulled the tubing to 2262' and pumped 39 barrels of gel and 35 sacks of cement with 1 sack of cottonseed hulls. Had cement from 2262' to 1955' and gel from 1955' to 298'. Returned to the well on 1-25-06 and shot the casing at 1022', moved up to 310' and circulated 90 sacks of cement to surface and pulled the casing.

RECEIVED  
KCC DISTRICT #3  
JUN 27 2006 TCH  
CHANUTE, KS

**Perfs:**

Top	Bot	Thru	Comments
2198	2200		
2190	2192		
2164	2165		
2140	2142		
2119	2121		
2092	2095		
2054	2056		
2003	2005		
1935	1937		
1875	1877		

**INVOICED**  
DATE 7-6-06  
2007060017

Remarks:

Plugged through:

District: 03

Signed Taylor C. Herman  
(TECHNICIAN)

RECEIVED  
JUL 05 2006  
KCC WICHITA

PPT