

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-085-20073-00-00  
Spot: NESE Sec/Twnshp/Rge: 15-5S-15E  
1980 feet from S Section Line, 660 feet from E Section Line  
Lease Name: AMON Well #: 9-15  
County: JACKSON Total Vertical Depth: 2420 feet

Operator License No.: 33233  
Op Name: HEARTLAND OIL & GAS, INC.  
Address: 1610 INDUSTRIAL PARK DRIVE  
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2390	892	165 SX CMT
SURF	8.625	243		120 SX CMT

\$ 78.65

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/24/2006 8:00 AM  
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.  
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 2342' TO 2251', CMT FROM 2251' TO 1955', GEL FROM 1955' TO 250', CMT FROM 250' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/25/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

On 1-24-06 ran tubing and tagged bottom at 2330' and pumed gel from 2330' to 2250'. Pulled tubing to 2267' and pumped 39 barrels of gel and 35 sacks of cement with 1 sack of cottonseed hulls. Had cement from 2267' to 1963' and gel from 1963' to 300'. Returned to the well the following day and shot the casing at 892' and moved up to 310', circulated 90 sacks of cement to surface and pulled the casing.

RECEIVED  
KCC DISTRICT #3  
JUN 27 2006  
CHANUTE, KS  
TCH

Perfs:

Top	Bot	Thru	Comments
2198	2201		
2191	2193		
2165	2166		
2137	2139		
2114	2116		
2092	2094		
2065	2067		
2053	2055		
2010	2011		
2005	2007		

INVOICED  
DATE 7-6-06  
2007060017

Remarks:

Plugged through: TBG

District: 03

Signed Taylor C. Herman  
(TECHNICIAN)

RECEIVED  
JUL 05 2006  
KCC WICHITA

ACT